

NPIC/R-225/64

BLAGODATNOYE AMMUNITION DEPOT SOUTH AND OTHER INSTALLATIONS NEAR BLAGODATNOYE, USSR

SUMMARY

25X1D
25X1D
25X1D
The munitions storage site near Blagodatnoye, USSR (BE designation: Blagodatnoye Ammunition Depot South), appears essentially the same on photography of [REDACTED] as it did on photography of [REDACTED]. Only one storage building has been removed and two possible warehouses have been added in the warehouse area during the intervening time. Approximately 12 buildings have been built in the servicing and administration area adjacent to the warehouse area. The five groups of bunkers are apparently unchanged since photography of [REDACTED]. The bunkers gave the impression of being little used at that time, a condition that still prevails.

A small new site has been built 1.5 nautical miles (nm) south of the depot. The site has no obvious association with either the depot or grids located in the vicinity, but it is possible that the site could be a developmental or testing facility for munitions.

Three grids have been observed in the general vicinity of the depot. Only Grid No 2 is visible on photography of [REDACTED]. Both Grids No 1 and No 2 are visible on photography of [REDACTED]. Grid No 3 is barely discernible on photography of [REDACTED] but is probably about the same age as the other two grids. A probable fenced area near Grid No 3 contains 16 possible fuel tanks.

25X1D

25X1D
25X1D

INTRODUCTION

25X1D
25X1D
25X1D
25X1D
The primary purpose of this report is to update the description of Blagodatnoye Ammunition Depot South (44-16N 132-06E). The site of the depot has been described in an earlier report 1/ which was based on poor-quality [REDACTED] photography. The present report, based on [REDACTED] photography, contains a description of the changes which have occurred since [REDACTED] and also reveals the presence of certain objects which, though present in [REDACTED] were not readily discernible at that time. For example, three groups of bunkers west of the depot's warehouse area were not illustrated in the previous

report, but they were present at the time of the [REDACTED] photography. Also, parts of the servicing and administration area are obscure on the [REDACTED] photography so that it is not possible to make a detailed, valid comparison of these areas with the same areas observed on [REDACTED] photography of [REDACTED].

The second purpose of the report is to describe three grids, a new site, and a probable fenced area in the vicinity of the Blagodatnoye Ammunition Depot South. The location of these installations and their spatial relationship is shown in Figure 1.

25X1D

25X1D

25X1
25X1D

Declassification Review by NIMA / DoD

NPIC/R-225/64




FIGURE 1. INSTALLATIONS NEAR BLAGODATNOYE, USSR, [REDACTED]

25X1D

NPIC/R-225/64

BLAGODATNOYE AMMUNITION DEPOT SOUTH

25X1A

Blagodatnoye Ammunition Depot South (BE No [REDACTED]) is located approximately 3 nm south of the village of Blagodatnoye and about 10 nm south of the town of Khorol in Primorskiy Kray, USSR (Figure 1). The depot comprises a separately fenced warehouse area, five

bunkered storage areas, and a servicing and administration area. A rail spur from the Khabarovsk-Vladivostok section of the Trans-Siberian Railroad terminates at the depot (Figures 2 and 3).




FIGURE 2. BLAGODATNOYE AMMUNITION DEPOT SOUTH, [REDACTED]

NPIC H-9007 (4/64)

25X1D

NPIC/R-225/64

Warehouse Area. The warehouse area consists of an irregular, fenced compound of about 680 acres; it contains 28 storage buildings of which 25 are set in recesses and are probably revetted. Three conventional warehouse-type buildings located in the northeastern part of the

warehouse area are not set in recesses and are probably not revetted. They measure approximately 200 by 55 feet. The other 25 storage buildings measure approximately 145 by 50 feet. Since two possible warehouses have been constructed on the western side of the

25X1D




FIGURE 3. LAYOUT OF BLAGODATNOYE AMMUNITION DEPOT SOUTH.

NPIC H-9008 (4/64)

25X1D

25X1D

25X1

NPIC/R-225/64

compound. No ventilating devices are discernible on any of the buildings. The total floor-space of the warehouses is approximately 214,250 square feet.

Bunkered Storage Areas. Approximately 63 bunkers, arranged in five groups, are located north and west of the warehouse area. Each group of bunkers is secured by a single fence. On poor-quality photography of [REDACTED] the bunkers appear as low, earth-mounded rectangular structures protruding a few feet above ground level; some of the bunkers are surrounded by a low earth revetment, apparently for drainage control. In [REDACTED] the bunkers appeared to be abandoned. Measurements made on this photography suggest that each bunker is about 40 by 20 feet; the earth mounding and associated revetments obscure the exact outlines of the structures. On photography of [REDACTED] the bunkers are poorly defined, irregular objects arranged in five arcuate patterns. The bunkered storage gives the impression of being little used. Inasmuch as the facility is located within

18 nm of three airfields, it is probable that the bunkers were designed and built for bomb storage.

Servicing and Administration Area. About 24 buildings are located between the warehouse and bunkered storage areas of the depot; approximately 12 of the buildings have been constructed since [REDACTED]. These buildings probably house the servicing and administration functions of the depot. The large number and varied configuration of the nonstorage-type buildings suggest that the depot is engaged in the servicing, renovation, or modification of the munitions stored there.

Security. A wide security strip has been cleared nearly all the way around the warehouse area of the depot. A possible interior fence has been erected that divides the warehouse area into approximately two equal parts. The security fence at the southern end of the warehouse area has been straightened since [REDACTED] a storage building has been removed to permit the fence realignment.

OTHER INSTALLATIONS


New Site. A new site is situated approximately 1.5 nm south of the Blagodatnoye Ammunition Depot South (Figure 1). The site consists of seven buildings of various sizes and five rectangular pads; the pads are located along an extension of the access road (Figure 4). This site was under construction in [REDACTED] four of the five pads were present at that time. The site has no apparent relationship to the Blagodatnoye Ammunition Depot South. The pads suggest parking spaces for mobile testing or metering equipment such as radars, telemetry receivers, and similar equipment.

Grids. Three grids, observed on [REDACTED] photography in the vicinity of the Blagodatnoye Ammunition Depot South, are designated Grids No 1, 2, and 3 (Figure 1). All three grids are located in very rough terrain, which is covered with scrub vegetation. Also, in all three grids the spacing of the grid lines is of the same order of magnitude, but the actual distances between adjacent lines are variable.

Grids No 1 and 2 are visible on earlier photography; Grid No 2, similar in area and spacing to Grid No 1, is visible on [REDACTED] photography and both Grids No 1 and 2 are visible on photography of [REDACTED]. Grid No 3 is barely discernible on [REDACTED] photography. It is probable that this grid was more

25X1

NPIC/R-225/64



NPIC H-9009 (4/64)

FIGURE 4. NEW SITE, [REDACTED]

25X1D

extensive in the past and has been partially effaced by erosion. The lines making up Grids No 1 and 2 are oriented in a north-south and east-west direction, while those of Grid No 3 are oriented in a northwest-southeast and northeast-southwest direction. A double cleared line around the perimeter of the two larger grids may be a firebreak or a security line under construction.

The northeastern edge of Grid No 1 is approximately 1.5 nm west of the Blagodatnoye Ammunition Depot South; the grid extends westward for about 3.7 nm. Its maximum north-south dimension is about 3.3 nm. Figure 5 shows the configuration and spacing of this grid.


Probable Fenced Area. A rectangular area, approximately 800 by 600 feet, probably fenced, is situated on the southeastern edge of Grid No 3 (Figure 1). Within this area are 16 small, regularly spaced white spots which may indicate buried tanks of some kind, possibly fuel tanks for one of the nearby airfields.

25X1D


NPIC/R-225/64

CONCLUSIONS

The following conclusions may be drawn from the interpretations presented in this report:




2. The new site south of the depot is probably not an additional storage facility and it has no apparent relationship to the depot or to the grids in the vicinity.



25X1B

REFERENCES

PHOTOGRAPHY




25X1D

MAPS OR CHARTS

ACIC. US Air Target Chart, Series 200, Sheet 0282-21HL, 3d ed, Jan 63, scale 1:200,000 (SECRET)

DOCUMENT



25X1

REQUIREMENT

CIA. C-SI4-81,005

NPIC PROJECT

N-113/64

TOP SECRET

Approved For Release 2004/05/12 : CIA-RDP78B04560A002000010050-8

Approved For Release 2004/05/12 : CIA-RDP78B04560A002000010050-8

TOP SECRET

TOP SECRET

Copy 106
7 Pages

NPIC/R-225/64

April 1964

PHOTOGRAPHIC INTERPRETATION REPORT

BLAGODATNOYE
AMMUNITION DEPOT SOUTH
AND OTHER INSTALLATIONS
NEAR BLAGODATNOYE, USSR



CIA




DIA

25X1



NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



TOP SECRET